SAMPLE ASSEMBLY DRAWINGS

ASSEMBLY DRAWINGS FOR A 42'W X 16'-2"H EAVE X 48'L KELLY KLOSURE BUILDING

K.K. ORDER #: P.O. #:

1) BUILDING STRUCTURE

A) BUILDING STRUCTURAL DESIGN CRITERIA

a) BUILDING CODE: 2009 IBC

b) ROOF LOAD: 20 PSF (GROUND SNOW LOAD)

SNOW DRIFT LOAD: NONE

) WIND LOAD: 90 MPH (3 SECOND GUST)

) SEISMIC: DESIGN CATEGORY "B", SOIL SITE CLASS "D"

f) OCCUPANCY CATEGORY: I

B) THIS BUILDING HAS BEEN DESIGNED IN ACCORDANCE WITH THE BUILDING CODE AND BASIC STRUCTURAL DESIGN DATA LISTED ABOVE. THE BUILDING HAS BEEN DESIGNED AND ENGINEERED FROM A STRUCTURAL ASPECT ONLY. OTHER CODE COMPLIANCE ISSUES SUCH AS ENERGY EFFICIENCY, OCCUPANCY, EGRESS, HVAC, ELECTRICAL, MECHANICAL, FIRE SAFETY ETC. IS THE RESPONSIBILITY OF THE END USER OR ITS REPRESENTATIVES. MATERIAL SPECIFICATIONS ARE AVAILABLE UPON REQUEST.

IMPORTANT NOTES

PLEASE READ BEFORE BEGINNING ASSEMBLY OF BUILDING

WARRANTY WILL BE VOIDED IF THESE PROCEDURES ARE NOT FOLLOWED

Technical Support & Service

A Kelly Klosure Service Representative is just a phone call away.

Please feel free to call with any questions, suggestions or issues as they arise!

Please call 1-800-228-7230 and ask for Service during normal business hours.

If calling after hours, please leave a voice mail in the general mailbox.

Please include the Kelly Klosure Order Number shown to the left on this page when calling for service.

Damage & Shipping Shortages

Any damage or shipping shortages should be reported to Kelly Klosure within 15 days of delivery. Kelly will expedite replacement material. However, Kelly is not liable for replacement material purchased locally without prior approval.

Back Charges

Kelly Klosure must give prior approval of any work relating to shortages or errors in manufacturing. If prior approval is not given, back charges will be denied.

Exterior Fasteners

Due to vibration during the shipping process, some screws that hold the exterior steel sheeting to the panel frame may have been loosened. The building erector is to check and tighten all of the screws prior to building assembly. The screws are considered tight when the rubber washer is in complete contact with the sheeting and is not loose to the touch.

Bolt Installation

All bolts shall be "Snug Tight". A "Snug Tight" condition is the tightness that is attained with a few impacts of an impact wrench or the full effort of a crew member using an ordinary spud wrench to bring the connected plies into firm contact. Per ASTM A325, sufficient thread engagement is having the end of the bolt extending beyond or at least flush with the outer face of the nut.

Building Penetrations

Every effort was made by Kelly during the approval process to factory frame any required wall or roof penetrations, or otherwise ensure that framing will not be interfered with for field cut penetrations. Prior approval and instructions for modification must be obtained from Kelly before cutting or modifying any structural steel framework, otherwise the warranty will be void.

Manufacturer's Disclaimer

The manufacturer has designed and engineered this system. Variations and/or modifications to the system or components will void and nullify any and all warranties, both written and/or implied, and liability for defects in the system and it's components. Manufacturer further accepts no responsibility and/or liability for obtaining or maintaining local, regional or national building permits, inspections or documents that may be required.

Lightning Protection Disclaimer

Kelly Klosure Systems roof & wall panels are manufactured from Galvalume® coated steel. To prevent galvanic corrosion, the roof and wall panels must not come into contact with, or water runoff from, copper, lead or copper bearing brasses. For lightning protection, aluminum conductors and aluminum or stainless steel clamps and fixtures are compatible with Galvalume® coated steel.

DRAWING INDEX

PAGE #1	PANEL & PANEL RACK HANDLING TIPS
2	BASIC BUILDING COMPONENTS
3	ELEVATIONS
4	MATERIALS LIST
5	BUILDING LAYFLAT
6	FOUNDATION PREPARATION PLAN VIEW
7	BASE SECTIONS
8	DOOR INSTALLATION INSTRUCTIONS
9	PLAN VIEW & DETAILS
10	CROSS-SECTION
11	CROSS-SECTION DETAILS
12	ROOF FRAMING PLAN VIEW
	SUPPLEMENT SHEETS
SS-1	BUILDING ASSEMBLY LIFTING INSTRUCTIONS
SS-2	LIFTING ANGLE CAPACITIES
SS-3	TIPPING FEET INSTALLATION INSTRUCTIONS
SS-4	BUILDING FLASHING INSTALLATION INSTRUCTIONS
SS-5	BASE FLASHING INSTALLATION ISOMETRIC
SS-6	BASE FLASHING INSTALLATION ISOMETRIC (AT DOORS
SS-7	BASE FLASHING CORNER CAP INSTALLATION
SS-8	DOUBLE DOOR FLASHING INSTALLATION
SS-9	EAVE FLASHING & CLOSURE CAP INSTALLATION
SS-10	GUTTER & DOWNSPOUT LAYFLAT
SS-11	GUTTER & DOWNSPOUT INSTALLATION INSTRUCTIONS
SS-12	GUTTER & DOWNSPOUT INSTALLATION DETAILS
SS-13	RIDGE CAP INSTALLATION INSTRUCTIONS

EQUIPMENT DOOR FLASHING INSTALLATION

LIGHT TRANSMITTING ROOF PANEL INSTALLATION

SS-14

SS-15


	T001 ::0=
	TOOL LIST
Qty.	Description
1	TIN SNIPS
4	SPUD WRENCH (1/4" - 3/4" TAPER W/ CRESCENT WRENCH)
2	1/2" DRIVE RATCHETS
2 2	3/4" SOCKETS 1 1/16" SOCKETS
2	ELECTRIC IMPACT WRENCH (1/2" DRIVE)
1	ROTARY HAMMER DRILL (MINIMUM 6 AMP, SDS STYLE)
lil	1/2" SDS MASONRY DRILL BIT (MINIMUM LENGTH 10")
i	SLEDGE HAMMER
1	3 LB HAMMER
2	C-CLAMP VISE GRIPS
2	C-CLAMP W/ 4"-6" OPENING
1	TAG LINE ROPE (75'-0" LONG)
	PHILLIPS SCREWDRIVER
1 1	STANDARD SCREWDRIVER BY DUILLING SCREWDRIVER (FOR DOOR LINGE AD ILLETMENT)
	P3 PHILLIPS SCREWDRIVER (FOR DOOR HINGE ADJUSTMENT) ELECTRIC DRILL
lil	9/16" STEEL DRILL BIT
lil	11/16" STEEL DRILL BIT
1	CUTTING OIL
2	3/4" WRENCHES
2	1 1/16" WRENCHES
2	5/16" NUT DRIVERS
2	3/8" NUT DRIVERS
1	100'-0" LONG TAPE MEASURE
1 2	CHALK LINE STEP LADDERS
1	CAULKING GUN
lil	STANDARD RIGGING
1	CHAINFALL RIGGING
1	FORK LIFT (TELE-HANDLER)
2	SCISSOR LIFT
1	ARTICULATING BOOM LIFT
1	CRANE (CAPACITY DEPENDING ON WEIGHT OF PICKS)
1	COME ALONG
1	WOOD DUNNAGE (4X4 LUMBER)
2 1	LARGE CROWBARS RIVET GUN
屵ᆜ	
L	ROLL-UP DOOR INSTALLATION TOOLS
- OF	TIONAL METHODS FOR ATTACHING DOOR TRACK TO JAMB:
-	OPTION #1: WELDED CONNECTION (WELDING EQUIPMENT NEEDED)
	OPTION #2: DRILLING & BOLTING (MAGNETIC BASE DRILL
	& CUTTING OIL RECOMMENDED)
	6" DRILL BITS (FOR DRILLING JAMBS FOR 1/2" BOLTS)
	1/2" WINDING BARS
	ING (TO INSTALL CURTAIN ON THE BARREL) DE GRIPS (2 PAIR MINIMUM)
	JE GRIPS (2 PAIR MINIMUM) ATER LEVEL OR STRING LINE LEVEL (WATER LEVEL IS RECOMMENDED)
	OMPLETE SOCKET SET
	OMPLETE WRENCH SET
	ANDARD & PHILLIPS SCREWDRIVERS
	RILL W/ COMPLETE SET OF BITS
- IMI	PACT WRENCH
-UT	ILITY KNIFE


FOR ELECTRIC OPERATOR
- WIRE STRIPPER
- CHAIN BREAKER

IMPORTANT NOTE: OVERHEAD DOORS ARE <u>SUPPLIED</u> ONLY!

INSTALLATION & SERVICE IS BY OTHERS!

(INSTRUCTIONS FOR OVERHEAD DOOR ARE INCLUDED WITH THE DOOR)





PANEL & PANEL RACK HANDLING TIPS



UNLOADING & LIFTING PANEL RACKS WITH A FORKLIFT

UPPER RACKS SHOULD BE REMOVED FROM THE TRUCK FIRST & PLACED AROUND THE WORKING AREA.



STORING PANEL RACKS IN STACKED POSITIONS


WHEN PANEL RACKS ARE STORED IN A STACKED POSITION (ONE ON TOP OF THE OTHER) ON SITE. THE FEET OF THE UPPER RACK MUST NEST INTO THE UPPER END OF THE BOTTOM RACK FRAMING (AS SHOWN). THIS KEEPS RACKS SPACED, MAINTAINING A PROTECTION ZONE FOR THE SHEETING OVERLAPS.

UPPER RACK FOOT



PROTECTED ZONE -

BOTTOM RACK FRAME




REMOVING PANELS FROM RACKS


WHEN PANEL RACKS ARE REMOVED FROM THE TRUCK AND PLACED AROUND THE STAGING AREA. THE FRONT TWO CORNERS OF EACH RACK SHOULD BE BLOCKED UP. THIS PREVENTS PANELS FROM TIPPING OUT AS PANELS ARE REMOVED. IF THIS IS NOT DONE THEN THERE IS THE POTENTIAL FOR PANEL DAMAGE.

LIFTING PANEL RACKS WITH SLINGS

AN OPTIONAL METHOD OF UNLOADING PANELS IS SHOWN IN THIS ILLUSTRATION. USING SLINGS HUNG FROM A CRANE OR CHERRY PICKER INSTEAD








FORKLIFT FORKS

SHEETING OVERLAPS

SEPARATING PANEL RACKS

WHEN LIFTING RACKS ONE OFF THE OTHER WITH A FORKLIFT. SPECIAL CARE MUST BE TAKEN TO PREVENT THE FORKS OF THE FORKLIFT FROM DAMAGING THE SHEETING OVERLAPS THAT PROTRUDE ABOVE THE BOTTOM PANEL RACKS. THIS MATERIAL IS MORE SUSCEPTIBLE TO DAMAGE THEN THE





REMOVE |

OF A FORKLIFT TO UNLOAD PANEL RACKS FROM - BLOCKING

FOUGH BY DESIGN. CUSTOM BY CHOICE. Mfgr. by Kelly Group, Inc. P.O. Box 1058 Fremont, NE 68026 Phone: 800-228-7230

PANEL & PANEL RACK ᆼ SKET SAMPLE ASSEMBLY DRAWINGS





MATERIALS LIST

Qty			Description	
20	3224		Panel. 3'x22'-6"x4"	
RP-1	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
4	3224	22R	Panel, 3'x22'-6"x4"	Outer Roof
RP-2	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	Outer Roof
8 8	3224	Sky	Panel. 3'x22'-6"x4"	Light Panel
RP-3	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	Light Fahei
32	3164	113	Panel, 3'x16'-2"x4"	
WP-1	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	271.5	113	Gable Panel 2'-3"x16'-3.7/8"/17'-1"	
RG-1 2'-3"	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	LG1-16-3	113	Gable Panel 3'x16'-3.7/8":17'-4.1/16"	
RG-1	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
2	LG1-16-3	113	Gable Panel 3'x16'-3.7/8";17'-4.1/16"	
LG-1	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	2710	RSO	Gable Panel 3'-9"x17'-1"/18'-4.1/4"	3'x7' P. Door (HRSO)
RG-2 3'-9"	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	3 X/ 1 : D001 (11K3O)
1	271.5	DSO	Gable Panel 6'-0"x17'-1"/18'-4.1/4"	5'8"x7' Double Door
RG-2 6'-0"	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	36 X7 Double Door
2	LG2-16-3	113	Gable Panel 3'x17'-4.1/16":18'-4.1/4"	
LG-2	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	RG3-16-3	113	Gable Panel 3'x18'-4.1/4";19'-4.7/16"	
RG-3	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
2	LG3-16-3	113	Gable Panel 3'x18'-4.1/4";19'-4.7/16"	
LG-3	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
2	RG4-16-3	113	Gable Panel 3'x19'-4.7/16":20'-4.5/8"	
RG-4	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
2	LG4-16-3	113	Gable Panel 3'x19'-4.7/16":20'-4.5/8"	
LG-4	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	RG5-16-3	113	Gable Panel 3'x20'-4.5/8":21'-4.13/16"	
RG-5	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	LG5-16-3	113	Gable Panel 3'x20'-4.5/8";21'-4.13/16"	
LG-5	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	RG6-16-3	113	Gable Panel 3'x21'-4.13/16";22'-5"	
RG-6	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	LG6-16-3	11.5	Gable Panel 3'x21'-4.13/16":22'-5"	
LG-6	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	RG7-16-3	110	Gable Panel 3'x22'-5";23'-5.3/16"	
RG-7	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	LG7-16-3	110	Gable Panel 3'x22'-5":23'-5.3/16"	
LG-7	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
1	RG5-16-3	C8	Gable Panel 3'x20'-4.5/8":21'-4.13/16"	8"Channel
RG-5J	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	o Chamer
1	LG5-16-3	C8	Gable Panel 3'x20'-4.5/8";21'-4.13/16"	8"Channel
LG-5J	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	o Chamici
1	27163	113	Middle Gable 12'x5'-4.13/16"/7'-5.3/16"	
MG-1	29LS	I15	29Ga Light Stone Sht 1.1/2" Insul.	
4	0226	A25	Erection Angle, 22'-6"	L2.1/2x2.1/2x3/16
GEA	0220	1120	22'-5.1/2"L	EE.1/EAE.1/EAJ/10
4	0162	A25	Erection Angle, 16'-2"	L2.1/2x2.1/2x3/16
CEA	0102	1143	16'-1.1/2"L	LL.1/2A2.1/2A3/10
Qty			Description	

GEA	0220	22'-5.1/2"L	L2.1/2X2.1/2XJ/10
4	0162	A25 Erection Angle, 16'-2"	L2.1/2x2.1/2x3/16
CEA Otv		16'-1.1/2"L Description	
Qty 1		Set Assembly Drawings (w/MSDS Sheets)	
2	Bottle	Touch Up Paint - Trim & Sheets	Light Stone
2	Bottle	Touch Up Paint - Trim & Sheets	Hawaiian Blue
1	Pint	Touch Up Paint - 17im Touch Up Paint - Panel Frames	Red Primer
1	Pint	Touch Up Paint - Paner Frames Touch Up Paint - Door	Mfg. Door Gray
1	1 1111	S. Parker Door Knob	g. Door Gray
1		S. Parker Door Closure	
34		Outer Closure Strip	Imperial Rib
8	Rolls	1/2" x 1" Base Seal - 25Ft	- Inportation
3	Tubes	Silco Caulking - Clear	
l		ng Bolts	
960		1/2"x1" Bolt, Zinc Plated	
960		1/2" Nut, Zinc Plated	
1	Set	Picking Angles (2-Large/2-Small)	
160		1/2" Washer	
l	S2 Br		
16	0015	Standard 3' S2 Ridge Angle	Formed Plate
32	0025	Standard 3' S2 Eave Angle	Formed Plate
192		1/2"x1" Bolt, Zinc Plated	
192		1/2" Nut, Zinc Plated	
14	42RB	S2 Ridge Brace	12'-3.11/16"L (L4x4)
26	42KB3	S2 Knee Brace	8'-6"L (L4x3)
94		3/4" x 2" A325 Bolt, Plain	
94		3/4" A563 Nut, Plain	
	Cookson Equ	uipment Door 12 Wide x	16 High
1		Cookson Roll-Up Equipment Door w/Hdwe	
5		Equipment Door Flashing	Hawaiian Blue
50		#4 Tek Screw	Hawaiian Blue
50		1/4" x 1.1/4" Bolt, Zinc Plated	
50		1/4" Nut, Zinc Plated	
44	Lf.	2" Brush Weatherstripping	
44	Lf.	Aluminum Retainer 1" 45 Degree	
88	p. 17.11	#5 Tek Screw	
	Building		*** **
5		10' Formed Ridge Cap	Light Stone
18		10' Corner Caps	Hawaiian Blue
10		10' Eave Flashing	Hawaiian Blue
20		10' Base Flashing	Light Stone
4		Base Flashing Corners	Light Stone
4		Closure Cap	Hawaiian Blue
2		Gable End Cap	Hawaiian Blue
16		Light Lap Cap	Light Stone
150		#8-18 x 1/2 T-2 Screw	Light Stone
500	101	#8-18 x 1/2 T-2 Screw	Hawaiian Blue
8 2	10' 5'	Open ended gutter sections	
2 2	5' 5'	Gutter section w/ Right endap & outlet	
4	16'	Gutter section w/ Left endap & outlet	
4	10	Box Downspouts	

Downspout support bracket

1) FOUNDATIONS

A) RECOMMENDED FOUNDATION SIZE IS GIVEN ON THE FOUNDATION PLAN VIEW PAGE OF THIS SET.

a) OUTSIDE DIMENSIONS AS SHOWN ARE REQUIRED TO ACCEPT BUILDING BASE FLASHING AS SUPPLIED. A TOLERANCE OF + OR - 1/4" IS ACCEPTABLE. THE SLAB SHOULD BE LEVEL AROUND PERIMETER OF FOUNDATION WITH A TOLERANCE OF + OR - 1/4". ANY VARIANCE COULD CREATE A LEAKAGE PROBLEM AT BASE OF BUILDING.

- b) USERS ARE TO ESTABLISH SIZE AND REINFORCEMENT REQUIREMENTS FOR FOUNDATIONS TO ACCOMMODATE SITE SOIL CONDITIONS AND LOCAL FROST DEPTH.
- BUILDING ANCHOR BOLT REACTIONS ARE AVAILABLE UPON REQUEST.
- B) ANCHOR BOLTS
 - a) PRESETTING OF ANCHOR BOLTS IS NOT REQUIRED. ANCHOR BOLTS WILL BE INSTALLED AS THE BUILDING IS ERECTED. KELLY RECOMMENDS THE HILTI KH-EZ SCREW ANCHOR AS SHOWN ON THE BUILDING BASE SECTION ON THE BASE SECTIONS PAGE.
 - CONCRETE ANCHORS WILL BE SUPPLIED WITH THE BUILDING SHIPMENT.

2) PANEL COMPONENTS AND FINISHES

- A) PANEL FRAMES & STRUCTURAL STEEL COMPONENTS
 - a) ONE COAT, CORROSION RESISTANT, WATER REDUCIBLE, ALKYD EMULSION PRIMER
- B) EXTERIOR STEEL SIDING AND ROOFING
 - a) 29 GA. 3/4" RIBBED "IMPERIAL RIB", DOES NOT REQUIRE SEAL TAPE OR STITCH SCREWS AT OVERLAPS
 - b) SIDING AND ROOFING TO BE GALVALUME COATED WITH PRIMER AND SILICONE MODIFIED POLYESTER PAINT FINISH
- C) FACTORY INSTALLED INSULATION
 - a) INSULATION TO BE RIGID, CLOSED CELL, POLYISOCYANURATE WITH FOIL FACING
 - b) WALLS: 2" THICK (R-13)
 -) ROOF: 2" THICK (R-13)
-) FACTORY INSTALLED STEEL INSULATION LINER
- a) 28 GA. GALVANIZED STEEL
- b) INSTALLED IN WALLS AND ROOF

3) GUTTER SYSTEMS

A) GUTTER & DOWNSPOUTS ARE SUPPLIED BY KELLY AS SHOWN ON THE BUILDING ELEVATIONS (PAGE 3 OF 12).

NOTES:

IN COLD CLIMATES WHERE ICE AND SNOW BUILD UP IS A PROBLEM, KELLY RECOMMENDS HEAT TRACE TO PREVENT ICE BUILD UP IN THE GUTTERS AND SNOW GUARDS / BLOCKS TO PREVENT SNOW FROM SLIDING OFF THE ROOF AND DAMAGING THE GUTTERS. THIS MATERIAL, IF REQUIRED, IS TO BE SUPPLIED AND INSTALLED BY OTHERS.

4) PERSONNEL AND EQUIPMENT DOORS

A) 3"W X 7"H PERSONNEL DOOR FACTORY INSTALLED IN A 3"-9" WIDE WALL PANEL,

TYPE "A" SHOWN ON PLAN VIEW

a) DOOR FRAME: 16 GA. STEEL, GALVANIZED (A-60), PRIMED AND FINISH PAINTED

b) DOOR LEAF: 18 GA. STEEL, HONEYCOMB CORÉ, GALVANIZED (A-60), PRIMED AND FINISH PAINTED

c) *ENTRY LOCK: STANDARD LOCKSET, S.PARKER B9160 SERIES, STAINLESS STEEL

d) HINGES: (3) 4.5" BALL BEARING, STANLEY FBB179, US26D FINISH

e) *CLOSER: STANDARD, S.PARKER 954, ALUMINUM FINISH

f) DOOR SWEEP: STANDARD, MD DCV134, ALUMINUM FINISH

a) WEATHER STRIPPING: NONE

h) THRESHOLD: MANUFACTURER STANDARD 3/16" FORMED STEEL

(i) 5'-8"W X 7"H PERSONNEL DOOR FACTORY INSTALLED IN A 6'-0" WIDE WALL PANEL,

TYPE "A" SHOWN ON PLAN VIEW

a) DOOR FRAME: 16 GA. STEEL, GALVANIZED (A-60), PRIMED AND FINISH PAINTED

b) DOOR LEAF: 18 GA. STEEL, HONEYCOMB CORE, GALVANIZED (A-60),

PRIMED AND FINISH PAINTED

c) *ENTRY LOCK: STANDARD LOCKSET, S.PARKER B9160 SERIES, STAINLESS STEEL

HINGES (PER LEAF): (3) 4.5" BALL BEARING, STANLEY FBB179, US26D FINISH

CLOSER: STANDARD, S.PARKER 954, ALUMINUM FINISH
DOOR SWEEP: STANDARD, MD DCV134, ALUMINUM FINISH

) WEATHER STRIPPING: NONE


) FLUSH BOLTS: INACTIVE LEAF ONLY, STANDARD, IVES 458B, US26D FINISH

i) THRESHOLD: MANUFACTURER STANDARD 3/16" FORMED STEEL

1. (*) THESE ITEMS ARE FIELD INSTALLED TO PREVENT DAMAGE DURING SHIPMENT AND ERECTION

B) ROLL-UP EQUIPMENT DOORS ARE AS NOTED ON THE PLAN VIEW PAGE DOOR SCHEDULE.

EQUIPMENT DOORS ARE SUPPLIED ONLY. INSTALLATION AND SERVICE IS THE RESPONSIBILITY OF THE END USER. KELLY KLOSURE DOES NOT HAVE EXPERIENCE IN INSTALLATION OF EQUIPMENT DOORS AND THEREFORE CANNOT PROVIDE ASSISTANCE EXCEPT IN WARRANTY, SHIPPING SHORTAGES OR SHIPPING DAMAGE RELATED ISSUES.



THIS MATERIALS LIST IS FOR EXAMPLE PURPOSES

ONLY AND DOES NOT MATCH THE BUILDING SHOWN


IN THESE ASSEMBLY DRAWINGS.

OVERLAP DETAIL




Fax: 402-727-1363 Web: www.kellyklosure.com Mfgr. by Kelly Group, In P.O. Box 1058
Fremont, NE 68026
Phone: 800-228-7230 12 MATERIALS LIST 유 4 SHEET SAMPLE ASSEMBLY DRAWINGS 1/29/14

LEFT







NOTES:

1. SEE CROSS-SECTION PAGE FOR BOLT LOCATIONS.


16'-1 1/2" CORNER

ANGLE (50 LBS)

2. NOT ALL HOLES IN PANELS REQUIRE BOLTS.

:	(-		/Incline		TOILEN RY DESIGN	
Mfgr. by Kelly Group, Inc.	P.O. Box 1058	Fremont, NE 68026	Phone: 800-228-7230		Fax: 402-727-1363	Web: www.kellyklosure.com
PAGETTIE BLIII DING I AYFI AT			SHEET 6 OF 12		PROPRIETARY INFORMATION	THE DRAWNER IN EXERGENT CONTROL SHEER ACCURATION THE UNIT OFFICE INC. THE DRAWNER THE DESIGNATION OF THE USENS EXCEPTED THE THE WILL HOT BE WAVELED, CONTROL TOWNER TOWNER OFFICE AND OFFIC
SAMPLE ASSEMBLY DRAWINGS				BUYER:		K.K. ORDER NUMBER: BUYER P.O. NUMBER:
DRAWN BY: APC	DATE: 1/29/14	APPROVED BY:	REVISION: 00	DATE: 1/29/14	SCALE: 3/32" = 1'-0"	<.K. QUOTE NUMBER:

CUSTOM BY CHOICE.





ᆼ

SKET

SAMPLE ASSEMBLY DRAWINGS

1/29/14


THIS DRAWING & THE DESIGNI OF NE. THEY ARE PROVIDED ON REPRODUCED, COPIED, LOANED, WAY PERMITTED BY CONSENT KELLY GROUP, INC. OF NE. MAKE

BASE CONNECTION HOLE

BASE CONNECTION HOLE

ATTENTION INSTALLER:

DOOR PANEL MUST BE POSITIONED AND ADJUSTED IN THE FIELD. DUE TO CONDITIONS OF THE FOUNDATION / FLOOR, WE HAVE NO CONTROL OVER PROPER ALIGNMENT OF DOOR PANEL.



DURING BUILDING ASSEMBLY DO NOT INSTALL ANCHOR BOLTS AT THESE LOCATIONS UNTIL DOOR HAS BEEN PROPERLY ALIGNED.

BEFORE DOOR PANEL IS TO BE ANCHORED, ASSEMBLE AND ERECT THE CORRESPONDING ROOF PANELS AND ACCESSORIES WITHIN THIS AREA.

ANY INFIELD REPAIRS OR MODIFICATIONS DONE BY THE INSTALLER ARE THE SOLE RESPONSIBILITY OF THE INSTALLER.

NOTE:

IF FACTORY WELDED NUTS IN DOOR PANEL STRIP OUT DURING INSTALLATION, DRILL OUT HOLE & USE SUPPLIED BOX BOLTS FOR DOOR PANEL TO ADJACENT PANEL CONNECTION.

FACTORY QUALITY CONTROL

DOORS ARE INSPECTED AT THE MANUFACTURING FACILITY FOR SQUARENESS AND PROPER DIMENSIONS BEFORE SHIPMENT. IF PRODUCT DAMAGE IS INCURRED DURING SHIPMENT, THIS DAMAGE MUST BE NOTED ON THE RECEIVING NOTICE AT THE TIME OF OFF LOADING AT THE BUILDING SITE. THE MANUFACTURER MUST BE NOTIFIED OF SUCH DAMAGE IMMEDIATELY.


IMPORTANT NOTE: OVERHEAD DOORS ARE SUPPLIED ONLY!


INSTALLATION & SERVICE BY OTHERS!


(INSTRUCTIONS FOR OVERHEAD DOOR ARE INCLUDED WITH THE DOOR)


FOR FACTORY ASSISTANCE IN DOOR
ALIGNMENT CALL 800-228-7230


	(-)					TOILEM RY DESIGN CILS		
Mfgr. by Kelly Group, Inc.	P.O. Box 1058	Fremont, NE 68026	1000	Phone: 800-228-7230		Fax: 402-727-1363		Web: www.kellyklosure.com
PAGETTIE: DOOR INSTALLATION				SHEFT & OF 19			THIS DRAWING & THE DESIGN IT COVERS ARE THE EXCLUSIVE PROPERTY OF KELLY GROUP, INC. OF NEITHEY ARE DEPARTMENT ONLY ON THE LIBERGE PYSICES ACCEPTANT THAT THEY WILL NOT BE	REPACTIVED, COPIET, LONGO, ENTITE, CHARLO, ENTITE, CHARLO, RETOVIET USE DE LA LOCAL MED WAY FERRALTED BY COMBENT OF KELLY RROLP, INC. OF NE. MAKES NO REPRESENTATION REGARDING DRAWING SOLLE & ACCUPACY.
OMECT THE SAMPLE ASSEMBLY DRAWINGS							K K CROFR NIMBER:	
PROJECT TITLE SAMP	DATE: 1/29/14	PPROVED BY:	UAIE	REVISION: 00	DATE: 1/29/14 BUYER:	SCALE: 1" = 1'-0"		.K. QUOTE NUMBER:















RIDGE ANGLE PICKING LUG

H.D. LUG MATERIAL: 1/4" A36 STEEL WITH 3/8" LUG PLATE STANDARD LUG MATERIAL: 3/16" A36 STEEL WITH 1/4" LUG PLATE

CAPACITY: 5,000 LBS ULTIMATE STRENGTH FOR USE AS LIFE SAFETY TIE-OFF POINT



SMALL LIFTING ANGLE

MATERIAL: 4" X 3" X 1/2" A36 STEEL ANGLE

CAPACITY: 2,000 LBS WITH 1/2" GRADE 5 BOLT, NUT & WASHERS


LARGE LIFTING ANGLE


MATERIAL: ∠4" X 3" X 1/2" A36 STEEL ANGLE W/ STIFFENER PLATES

CAPACITY: 7,700 LBS WITH 5/8" A325 BOLT & NUT

PHOTOM BY PURIFE
_
TOILD BY DESIGN
_

	_	7			
Mfgr. by Kelly Group, Inc. P.O. Box 1058	Fremont, NE 68026	Phone: 800-228-7230		Fax: 402-727-1363	Web: www.kellyklosure.com
PAGE TILE LIFTING ANGLE CAPACITIES		SHEET SS.2 OF SS.15		PROPRIETARY INFORMATION	THE DAYWING A THE EBBOAT LOCKHER ARE THE EXCLUSIVE CHEMETRY OF KILLY GROUN, INC. THE DAYWING A THE EBBOAT COURSE AND A THE OFFICE AND A THEORY AND A THE OFFICE AND A THEORY
SAMPLE ASSEMBLY DRAWINGS					BUYER P.O. NUMBER:
PROJECT THE SAMPLE ASSI			BUYER:		K.K. ORDER NUMBER:
DRAWIN BY: APC DATE: 1/29/14	VED BY:	DATE: REVISION: 00	DATE: 1/29/14	SCALE: NO SCALE	K.K. QUOTE NUMBER:





BUILDING FLASHING INSTALLATION LOCATIONS

GUTTERS AND DOWNSPOUTS NOT SHOWN
SEE GUTTER INSTALLATION PAGES FOR INFORMATION

NOTE:

REMOVE PROTECTIVE FILM FROM FLASHING MATERIAL PRIOR TO INSTALLATION IF APPLICABLE

IMPORTANT NOTE:

OVERHEAD DOORS ARE SUPPLIED ONLY!

INSTALLATION & SERVICE BY OTHERS!

(INSTRUCTIONS FOR OVERHEAD DOOR ARE INCLUDED WITH THE DOOR)

FLASHING INSTALLATION SEQUENCE

(SEE PAGES DIRECTLY FOLLOWING THIS PAGE FOR INSTALLATION OF THE FOLLOWING PARTS)

- 1. BASE FLASHING SUPPLIED IN 10'-6" LENGTHS
- 2. BASE FLASHING CORNER CAPS SUPPLIED AS SHOWN
- 3. CORNER CAPS @ WALL CORNERS
 TYPICALLY SUPPLIED IN 10'-6" LENGTHS
- 4. INSTALL PARTITION WALL & REMOVABLE ROOF LAP CAPS (IF APPLICABLE)
- 5. EAVE FLASHING
 SUPPLIED IN 10'-6" LENGTHS
 INSTALL GUTTERS AND DOWNSPOUTS
 DURING THIS STEP IF SUPPLIED
 (SEE THE GUTTER INSTALLATION PAGES FOR DETAILS)
- 6. CORNER CAPS @ ROOF CORNERS
 TYPICALLY SUPPLIED IN 10'-6" LENGTHS
- 7. CLOSURE CAPS
 SUPPLIED AS SHOWN
 (THERE WILL BE DIFFERENT CLOSURE CAPS
 FOR THE RIGHT AND LEFT SIDE AS YOU FACE
 THE GABLE END WALL OF THE BUILDING)
- 8. GABLE END CAP SUPPLIED AS SHOWN
- 9. RIDGE CAP SUPPLIED IN 10'-6" PIECES
- 10. INSTALL ALL REMAINING MATERIAL INCLUDING EQUIPMENT DOOR FLASHING, DOUBLE DOOR VERTICAL FLASHING & ANY OTHER MATERIAL REQUIRED.

EXISTING SLAB
BASE FLASHING
EQUIPMENT DOOR FLASHING

INSULATED UNINSULATED BUILDING

BASE FLASHING DOUBLE DOOR VERTICAL TRIM


GUTTER SECTION

GUTTER SUPPORT CHANNEL


BASE CORNER CAP



CORNER CAPS



EAVE FLASHING



CLOSURE CAPS



GABLE END CAP





Mfgr. by Kelly Group, Inc. P.O. Box 1058 Phone: 800-228-7230 Fremont, NE 68026 INSTALLATION INSTRUCTIONS **BUILDING FLASHING** ᆼ **SS-4** SHEET SAMPLE ASSEMBLY DRAWINGS 1/29/14


BASE FLASHING INSTALLATION

INSTALLATION INSTRUCTIONS:

- 1.) LOOSEN BOTTOM ROW OF SHEETING SCREWS (DO NOT REMOVE).
- 2.) SLIDE BASE FLASHING IN FROM END OF WALL. OVERLAP SECTIONS BY 2" AND CAULK AT FLASHING LAP JOINTS.
- 3.) TIGHTEN SHEETING SCREWS.

TIP: FOR LONGER WALLS, INSTALL BASE FLASHING AFTER EACH 12' SECTION OF WALL IS ERECTED


NOTE: BASE FLASHING MAY NEED TO BE FIELD TRIMMED FOR PROPER FIT.






Web: www.kellyklosure.com Mfgr. by Kelly Group, Inc. P.O. Box 1058 Fremont, NE 68026 Phone: 800-228-7230 **SS-15** INSTALLATION ISOMETRIC **BASE FLASHING** ᆼ **SS-5** SHEET SAMPLE ASSEMBLY DRAWINGS 1/29/14


BASE FLASHING CORNER CAP




STEP #1
INSTALL BASE FLASHING AS SHOWN,
EXTENDING EACH PIECE OUT TO THE
OUTER EDGE OF THE CONCRETE
FOUNDATION SHOWN.



STEP #3
INSTALL BASE FLASHING CORNER CAP
AS SHOWN. CAULK BETWEEN BASE FLASHING
AND CORNER CAP.




STEP #4
SCREW OR POP RIVET BASE
FLASHING CORNER CAP TO THE
BASE FLASHING IF NEEDED
FINISHED CORNER LAP



FIELD PREP BASE FLASHING CORNER CAP
BY TRIMMING OFF UNNEEDED PORTION. THIS
IS ACHIEVED BY MEASURING THE DISTANCE FROM
OUTER EDGE OF CONCRETE TO EDGE OF WALL PANEL
AT THE CORNER (SEE DETAIL #1). NOW APPLY THESE
MEASUREMENTS TO THE CAP AND TRIM OFF THE

UNNEEDED PORTION.




THIS PAGE IS TYPICAL
FOR BOTH INSULATED &
NON-INSULATED BUILDINGS

				THIEM BY		
Mfgr. by Kelly Group, Inc. P.O. Box 1058 Fremont, NE 68026	DEC. 000 000 2000	Friorie: 000-220-7230	1000	Fax: 402-727-1363		Web: www.kellyklosure.com
BASE FLASHING CORNER CAP INSTALLATION INSTRUCTIONS	17 00 L	SHEEL SS-7 OF SS-15		PROPRIETARY INFORMATION	THIS DRAWING & THE DESIGN IT COVERS ARE THE EXCLUSIVE PROPERTY OF KELLY GROUP, INC.	REPART LEES VERFORMENT PROPERTY OF RESERVED FOR STATEMENT OF THE USE OF THE WASHINGTON OF THE WASHINGT
ROLET ME. SAMPLE ASSEMBLY DRAWINGS		an north	BOTEK		V V OBORDIN MARCO.	
			,			

1/29/14

JESIGN. CUSTOM BY CHOICE.



TOUGH BY DESIGN. CUSTOM BY CHOICE.

Web: www.kellyklosure.com

Phone: 800-228-7230

SS-15

ᆼ


SS-9

SHEET

IMPORTANT NOTE:
ALL DOWNSPOUTS WILL NEED
TO BE FIELD LOCATED AND CUT
TO THE APPROPRIATE LENGTH.

IMPORTANT NOTE:

SEE "GUTTER & DOWN SPOUT INSTALLATION" PAGES FOR ANY INSTALLATION QUESTIONS.




GUTTER SYSTEM LAYFLAT

(SAME FOR OTHER SIDE)



	SAMPLE ASSEM	ASSEMBLY DRAWINGS	GITTER & DOWNSPOUT	Migr. by Kelly Group, Inc.	
1/29/14			I AVEI AT	P.O. Box 1058	
ED BY:				Fremont, NE 68026	
				DEC. 000 000 1000	
00			SHFF (3.7. 10 C) - 3.7. 15	Pnone: &uu-228-7230	
1/29/14	BUYER:				
NO SCALE			PROPRIETARY INFORMATION	Fax: 402-/2/-1363	
	ן או א סטענט או וואפנטי	BINED DO NIMBED	THIS DRAWING & THE DESIGN IT COVERS ARE THE EXCLUSIVE ROPERTY OF KELLY GROUP INC.		
OTE NUMBER:			REMOVEDED CONTROLLED C	Web: www.kellyklosure.com	



TYPICAL GUTTER SYSTEM

EXPLODED VIEW

GUTTER SYSTEM AND EAVE FLASHING INSTALLATION INSTRUCTIONS

IMPORTANT NOTES:


- 1. REFER TO <u>GUTTER SYSTEM LAYFLAT</u> PAGE FOR LOCATIONS OF EACH COMPONENT.
- 2. GUTTERS TO BE INSTALLED AT SAME TIME AS EAVE FLASHING.
- 3. CAULK AROUND ALL END CAPS AND BETWEEN EACH JOINT WITH SUPPLIED CAULKING.
- 4. SOME FIELD CUTTING OF COMPONENTS MAY BE NECESSARY TO ENSURE PROPER FIT.
- 5. IN COLD CLIMATES WHERE ICE AND SNOW BUILD UP IS A PROBLEM, KELLY RECOMMENDS HEAT TRACE TO PREVENT ICE BUILD UP IN THE GUTTERS AND SNOW GUARDS / BLOCKS TO PREVENT SNOW FROM SLIDING OFF THE ROOF AND DAMAGING THE GUTTERS. THIS MATERIAL IF REQUIRED IS TO BE SUPPLIED AND INSTALLED BY OTHERS.


GUTTER & DOWN SPOUT INSTALLATION PROCEDURE

- 1. LAYOUT GUTTER SYSTEM MATERIAL AS SHOWN ON THE <u>GUTTER SYSTEM</u> <u>LAYFLAT</u> PAGE. (SEE INDEX FOR PAGE #)
- 2. INSTALL GUTTER SECTIONS & EAVE FLASHING STARTING AT ONE END OF BUILDING. BE SURE TO INSTALL CLOSURE CAPS AT EACH END OF THE BUILDING BEHIND THE GUTTER SECTION. (SEE FLASHING INSTALLATION DETAILS)
- 3. TO INSTALL GUTTER SECTIONS & EAVE FLASHING; REMOVE FACTORY INSTALLED SCREWS AT THE END OF THE ROOF SHEETS. SLIDE EAVE FLASHING AND GUTTERS UNDER THE ROOF SHEET AND FOAM FILLER. REINSTALL SCREWS THROUGH ROOF SHEET, GUTTER, EAVE FLASHING AND INTO FRAME. BUTT THE ENDS OF THE GUTTER SECTIONS TOGETHER AS SHOWN ON THE "GUTTER INSTALLATION DETAILS PAGE".
- 4. CONNECT GUTTER SECTIONS USING THE SUPPLIED GUTTER SPLICES. INSTALL GUTTER END CAPS AND DOWNSPOUT OUTLETS IN THE CORRECT LOCATIONS. USE CAULKING AND SUPPLIED RIVETS TO SECURE. (THESE COMPONENTS CAN BE INSTALLED AFTER ALL GUTTER SECTIONS ARE IN PLACE OR WHILE THEY ARE BEING INSTALLED.)
- 5. AFTER ALL GUTTER SECTIONS ARE INSTALLED, BEGIN FASTENING GUTTER SUPPORT CHANNELS EVERY 3'-0" ON CENTER AT ROOF OVERLAP JOINTS. THESE CHANNELS SHOULD BE 1'-0" LONG.
- 6. INSTALL DOWN SPOUTS USING SUPPLIED DOWN SPOUT BRACKETS. USE SUPPLIED TEK SCREWS AND RIVETS TO FASTEN.



Web: www.kellyklosure.com Mfgr. by Kelly Group, Inc. P.O. Box 1058 Phone: 800-228-7230 Fremont, NE 68026 Fax: 402-727-1363 INSTALLATION INSTRUCTIONS **SS-15 GUTTER & DOWNSPOUT** ᆼ SHEET SS-11 SAMPLE ASSEMBLY DRAWINGS 1/29/14





EQUIPMENT DOOR OPENING FLASHING

TOUGH BY DESIGN. CUSTOM BY CHOICE.

Web: www.kellyklosure.com

Mfgr. by Kelly Group, Inc. P.O. Box 1058 Fremont, NE 68026

EQUIPMENT DOOR FLASHING INSTALLATION INSTRUCTIONS

SAMPLE ASSEMBLY DRAWINGS

1/29/14

Phone: 800-228-7230

SS-15

ᆼ

SHEET SS-14


IMPORTANT NOTE: OVERHEAD DOORS ARE SUPPLIED ONLY!

INSTALLATION & SERVICE IS BY OTHERS!

(INSTRUCTIONS FOR OVERHEAD DOOR ARE INCLUDED WITH THE DOOR)

INSTALLATION NOTES:

- 1. INSTALL EQUIPMENT DOOR TRIM BEFORE INSTALLING OVERHEAD DOOR.
- 2. ALL WEATHER-STRIPPING AND BRUSHES TO BE INSTALLED PER DOOR MANUFACTURERS INSTRUCTIONS.



EQUIPMENT DOOR ELEVATION

